



ENERGY SMART

HOME PERFORMANCE CONSULTING

PROJECT: 2924 Osprey Lane, Silverthorne, CO 80498

1. Air Sealing Time and Materials Estimate:

15 hours to include sealing of wall/ceiling penetrations, attic access, attic and vaulted ceiling recessed lights, bath vents, some door trim, outlets/switches, pet door, plumbing chase, door weather strip/sweeps/adjustments were possible.....\$750
Materials minus LED recessed light retrofit kits.....\$100
LED Retrofit kits (19).....\$190

2. Exterior Ceiling (Attic):

R38 fiberglass loose fill insulation to exterior ceiling over existing to bring to R50. R38 unfaced fiberglass batts over attic access.....\$2800

3. Attic knee walls:

R13 (2") spray foam over existing batts and framing for air and thermal seal.....\$700

Thank you for the opportunity to submit this proposal.

Mark Anderson @ EnergySmart

PO Box 2902, Frisco CO 80443

(970) 485-3327

Xcel Energy Contractor ID # 101944

Terms & Conditions Proposal Accepted by: _____

Date: _____